



# METRO COTABATO WATER DISTRICT

Gov. Gutierrez Avenue, Cotabato City, P.O. Box 657

Tel. No. (064) 4211070; Telefax. No. (064) 4213009

Email Add: [mcwd\\_procurement@yahoo.com](mailto:mcwd_procurement@yahoo.com)



## SUPPLEMENTAL / BID BULLETIN

### ADDENDUM NO. 21-07

#### **“Supply, Delivery, Installation, Testing & Commissioning of four (4) sets 250mmØ (10”Ø) Electro Magnetic Flow Meter with Data Logger for the Biniruan Bulk Water System Project”**

This Addendum No. 21-07 is being issued to add, clarify, modify or amend provisions in the Bidding Documents, which shall form an integral part thereof:

ORIGINAL	AMENDMENT
<p><b>Section VI. Schedule of Requirement (page 56)</b></p> <p><b>Delivery Date:</b> Delivery, Installation, Testing and Commissioning will be at the Three (3) Specified Locations for the Biniruan Bulk Water System Project (see attached locations – Annex “A”) within 90 calendar days after receipt of approved P.O./Notice to Proceed.</p> <p><b>Section VII. Technical Specification</b></p> <p>I. Specifications:</p> <p>A. FLOWMETER (page 57)</p> <p>b. Transmitter</p> <p>i. Type</p> <p>1. Remote up to 100m or longer</p> <p>B. DATA LOGGER</p> <p>a. Communication</p> <p>i. Programming and Downloading</p> <p>ii. GPRS to user specified FTP Site (Existing Primeweb)</p> <p>iii. Transmission Option: 4G or Better</p> <p>iv. Antenna Internal or External</p> <p>v. Must be ISO 4064 / OIML / Equivalent Standard Certified</p> <p>C. Accessories:</p> <p>a. Matting Flange with Bolts&amp; Nuts:</p> <p>ii. No. of Holes: ISO Standard (250mmØ = 8)</p>	<p><b>Section VI. Schedule of Requirement (page 56)</b></p> <p><b>Delivery Date:</b> Delivery, Installation, Testing and Commissioning will be at the Three (3) Specified Locations for the Biniruan Bulk Water System Project (see attached locations – Annex “A”) within <b>One Hundred Twenty (120) calendar days</b> after receipt of approved P.O./Notice to Proceed.</p> <p><b>Section VII. Technical Specification</b></p> <p>I. Specifications:</p> <p>A. Flowmeter (page 57)</p> <p>b. Transmitter</p> <p>i. Type</p> <p>1. Remote up to <b>50 Meters</b> or longer</p> <p>B. DATA LOGGER</p> <p>a. Communication</p> <p>i. Programming and Downloading</p> <p>ii. GPRS to user specified FTP Site (Existing Primeweb)</p> <p>iii. Transmission Option: 4G or Better</p> <p>iv. Antenna Internal or External</p> <p>C. Accessories:</p> <p>a. Matting Flange with Bolts&amp; Nuts:</p> <p>ii. No. of Holes: ISO Standard (250mmØ = <b>12</b>)</p>

Water Conserved Today is Water Abundant Tomorrow





# METRO COTABATO WATER DISTRICT

Gov. Gutierrez Avenue, Cotabato City, P.O. Box 657

Tel. No. (064) 4211070; Telefax. No. (064) 4213009

Email Add: mcwd\_procurement@yahoo.com



ORIGINAL	AMENDMENT
<p>e. Housing / Panel Box: (page 59)</p> <p>II. Terms and Conditions (page 59)</p> <p>4. Supply, Delivery, Installation and Commissioning must be within Ninety (90) calendar days after the receipt of the Approved Notice to Proceed (NTP).</p> <p>8. Only Three (3) sets of the Electromagnetic flow meters upon the advice of the Project in-charge will be initially installed on a specific &amp; identified locations. While the other One (1) set will be installed in replacement of any of the initially installed sets within six (6) months;</p> <p>Annex “A-1” (page 64)</p> <p>DELIVERY: SUPPLY, DELIVERY, INSTALLATION, TESTING AND COMMISSIONING SHALL BE WITHIN 90 CALENDAR DAYS UPON RECEIPT OF PURCHASE ORDER.</p>	<p>e. Housing / Panel Box: (page 59)</p> <p>iii. Material:</p> <ul style="list-style-type: none"> <li>1. Enclosure, Door, Brackets:           <ul style="list-style-type: none"> <li>a. Galvanized Plain Sheet Gauge 16</li> <li>b. Powder-coated</li> </ul> </li> <li>2. Color: BEIGE / BLUE / GRAY (as per client approval)</li> <li>3. Protection IP Rated : IP66</li> </ul> <p>iv. Design: Customized, subject to end-users approval</p> <p>f. Inclusions:</p> <ul style="list-style-type: none"> <li>i. Enclosure with Hinged door</li> <li>ii. 180° (Degrees) Door</li> <li>iii. Cam Lock</li> <li>iv. Data Logger Bracket</li> <li>v. Vent Slots</li> <li>vi. Safety Hasp</li> <li>vii. Padlock: Masterlock 1500id</li> </ul> <p>II. Terms and Conditions (page 59)</p> <p>4. Supply, Delivery, Installation and Commissioning must be within <b>One Hundred Twenty (120) calendar days</b> after the receipt of the Approved Notice to Proceed (NTP).</p> <p>8. Only Three (3) sets of the Electromagnetic flow meters upon the advice of the Project in-charge will be initially installed on a specific &amp; identified locations. While the other One (1) set will be installed in replacement of any of the initially installed sets, <b>after Six (6) to Nine (9) Months;</b></p> <p>Annex “A-1” (page 64)</p> <p><b>DELIVERY: SUPPLY, DELIVERY, INSTALLATION, TESTING AND COMMISSIONING SHALL BE WITHIN ONE HUNDRED TWENTY (120) CALENDAR DAYS UPON RECEIPT OF APPROVED NOTICE TO PROCEED (NTP).</b></p>





# METRO COTABATO WATER DISTRICT

Gov. Gutierrez Avenue, Cotabato City, P.O. Box 657

Tel. No. (064) 4211070; Telefax. No. (064) 4213009

Email Add: [mcwd\\_procurement@yahoo.com](mailto:mcwd_procurement@yahoo.com)



This Supplemental/Bid Bulletin shall form part of the Bidding Documents. Any provisions in the Bidding Documents inconsistent herewith is hereby amended, modified and superseded accordingly.

For the guidance and information of all concerned.

Issued this 19<sup>th</sup> of July, 2021 at Metro Cotabato Water District, Cotabato City, Maguindanao.

Reviewed and approved by:

  
WINSTON L. SAPAL  
BAC - Chairperson